								R	EVISI	ONS										
LTR					D	ESCR	IPTIO	N					DA	TE (YI	R-MO-	DA)		APPR	OVED	)
A	limits	s, table	e III. Ao	E F88 dd cas require	e outli	ine X.	Updat				delta			01-0	)2-26		Ra	aymon	d Mon	nin
В	MIL-PRF-38535 requirements. – Igt Add radiation features in section 1.5. Correct the wa figure 5. Update the boilerplate to include radiation h requirements. Editorial changes throughout jak						tion ha			ired		04-1	2-14		Thomas M. Hess		ess			
						-														
THE FRONT	PAG	E OF	THIS	DRA	WING	6 HAS	BEE	N RE	PLAC	ED.										
REV																				
SHEET																				
REV	В	В	В	В	В	В	В													
SHEET	15	16	17	18	19	20	21													
REV STATUS	5			RE∖			В	В	В	В	В	В	В	В	В	В	Α	Α	В	A
OF SHEETS				SHE	ET		1	2	3	4	5	6	7	8	9	10	11	12	13	14
PMIC N/A				PRE	PARE	ED BY														
				Marcia B. Kelleher				DEFENSE SUPPLY CENTER COLUMBUS COLUMBUS, OHIO 43218-3990												
STAI MICRC DRA		CUIT		CHECKED BY Ray Monnin							<u>http</u>	<u>)://ww</u>	<u>/w.ds</u>	<u>cc.dla</u>	<u>a.mil</u>					
		•		APF	PROV	ED BY	,													
THIS DF											<b>D 2 2</b>		u <del>.</del> -							
AVA FOR US	ILABLI SE BY	_			IV	lichael	A. Fr	ye								ADVA ABLE		D CN Ary	IUS,	
DEPAF AND AGEN DEPARTMEN		NTS OF TH		DRA	WING	6 APPI 89-0	ROVA 16-07	L DAT	E							ILICC		, 11 X I		
AMS	SC N/A	A		REV	ISION	I LEVE B					ZE <b>A</b>		.GE CC			5	962-	8956	61	
						U				SHE										
										3	. <b>C</b> I		1	OF	21					

#### 1. SCOPE

1.1 <u>Scope</u>. This drawing documents two product assurance class levels consisting of high reliability (device classes Q and M) and space application (device class V). A choice of case outlines and lead finishes are available and are reflected in the Part or Identifying Number (PIN). When available, a choice of Radiation Hardness Assurance (RHA) levels are reflected in the PIN.

1.2 <u>PIN</u>. The PIN is as shown in the following example:

For device classes M and Q: 5962 89561 01 Federal RHA Device Case Lead stock class designator outline finish type designator (see 1.2.1) (see 1.2.2) (see 1.2.4) (see 1.2.5) V Drawing number For device class V: 5962 89561 01 Federal RHA Device Device Case Lead stock class class outline designator type finish designator designator (see 1.2.4) (see 1.2.5) (see 1.2.1) (see 1.2.2) (see 1.2.3) V Drawing number

1.2.1 <u>RHA designator</u>. Device classes Q and V RHA marked devices meet the MIL-PRF-38535 specified RHA levels and are marked with the appropriate RHA designator. Device class M RHA marked devices meet the MIL-PRF-38535, appendix A specified RHA levels and are marked with the appropriate RHA designator. A dash (-) indicates a non-RHA device.

1.2.2 <u>Device type(s)</u>. The device type(s) identify the circuit function as follows:

Device type	Generic number	Circuit function
01	54AC161	Synchronous presettable binary counter

1.2.3 <u>Device class designator</u>. The device class designator is a single letter identifying the product assurance level as listed below. Since the device class designator has been added after the original issuance of this drawing, device classes M and Q designators will not be included in the PIN and will not be marked on the device.

Device class	Device requirements documentation
Μ	Vendor self-certification to the requirements for MIL-STD-883 compliant, non-JAN class level B microcircuits in accordance with MIL-PRF-38535, appendix A
Q or V	Certification and qualification to MIL-PRF-38535

STANDARD MICROCIRCUIT DRAWING	SIZE A		5962-89561
DEFENSE SUPPLY CENTER COLUMBUS COLUMBUS, OHIO 43218-3990		REVISION LEVEL B	SHEET 2

1.2.4 Case outline(s). The case outline(s) are as designated in MIL-STD-1835 and as follows:

Outline letter	Descriptive designator	Terminals	Package style
Е	GDIP1-T16 or CDIP2-T16	16	Dual-in-line
F	GDFP2-F16 or CDFP3-F16	16	Flat pack
2	CQCC1-N20	20	Square leadless chip carrier
Х	CDFP4-F16	16	Flat pack

1.2.5 Lead finish. The lead finish is as specified in MIL-PRF-38535 for device classes Q and V or MIL-PRF-38535, appendix A for device class M.

1.3 Absolute maximum ratings. 1/2/3/

Supply voltage range ( $V_{CC}$ ) DC input voltage range ( $V_{IN}$ ) DC output voltage range ( $V_{OUT}$ )	0.5 V dc to V <sub>CC</sub> + 0.5 V dc
Clamp diode current (I <sub>IK</sub> , I <sub>OK</sub> )	±20 mA
DC output current	±50 mA
DC V <sub>CC</sub> or GND current (per pin)	±50 mA
Storage temperature range (T <sub>STG</sub> )	
Maximum power dissipation (P <sub>D</sub> )	500 mW
Lead temperature (soldering, 10 seconds):	
Case outline X	+260°C
All other case outlines except case X	+245°C
Thermal resistance, junction-to-case $(\theta_{JC})$	See MIL-STD-1835
Junction temperature (T <sub>J</sub> )	+175°C <u>4</u> /

1.4 Recommended operating conditions. 2/3/5/

Supply voltage range ( $V_{CC}$ ) Input voltage range ( $V_{IN}$ ) Output voltage range ( $V_{OUT}$ )	+0.0 V dc to $V_{CC}$
Case operating temperature range (T <sub>C</sub> )	
Input rise or fall times:	
$V_{\rm CC} = 3.6$ V to 5.5 V	0 to 8 ns/V
Minimum setup time, Pn to CP ( $t_s$ ):	
$T_{\rm C} = +25^{\circ}{\rm C}, V_{\rm CC} = 3.0 {\rm V}$	11.0 ns
$T_{\rm C} = +25^{\circ}{\rm C}, V_{\rm CC} = 4.5 {\rm V}$	
$T_{\rm C} = -55^{\circ}$ C to 125°C, $V_{\rm CC} = 3.0$ V	
$T_{\rm C} = -55^{\circ}$ C to 125°C, $V_{\rm CC} = 4.5$ V	10.5 ns
Minimum hold time, Pn to CP (t <sub>h</sub> ):	
$T_{\rm C}$ = +25°C, $V_{\rm CC}$ = 3.0 V	0.0 ns
$T_{\rm C}$ = +25°C, $V_{\rm CC}$ = 4.5 V	1.5 ns
$T_{\rm C}$ = -55°C to 125°C, $V_{\rm CC}$ = 3.0 V	
$T_{\rm C} = -55^{\circ}$ C to 125°C, $V_{\rm CC} = 4.5$ V	1.5 ns

1/ Stresses above the absolute maximum rating may cause permanent damage to the device. Extended operation at the maximum levels may degrade performance and affect reliability.

2/ Unless otherwise noted, all voltages are referenced to GND.

3/ The limits for the parameters specified herein shall apply over the full specified V<sub>CC</sub> range and case temperature range of -55°C to +125°C.

- <u>4</u>/ Maximum junction temperature shall not be exceeded except for allowable short duration burn-in screening conditions in accordance with method 5004 of MIL-STD-883.
- 5/ Operation from 2.0 V dc to 3.0 V dc is provided for compatibility with data retention and battery back-up systems. Data retention implies no input transition and no stored data loss with the following conditions:  $V_{IH} \ge 70\% V_{CC}$ ,  $V_{IL} \le 30\% V_{CC}$ ,  $V_{OH} \ge 70\% V_{CC}$  @  $-20\mu$ A,  $V_{OL} \le 30\% V_{CC}$  @  $20 \mu$ A.

STANDARD MICROCIRCUIT DRAWING	SIZE A		5962-89561
DEFENSE SUPPLY CENTER COLUMBUS COLUMBUS, OHIO 43218-3990		REVISION LEVEL B	SHEET 3
DSCC FORM 2234			

# 1.4 <u>Recommended operating conditions</u> – Continued.

	a
70 141	
 1.5 ns	
5 0 pc	
 5.U NS	
10 pc	
 5.5 ns	
 6.0 ns	
4.5.4.5	
 10.5 NS	
00 rads (Si)/s)	

#### 2. APPLICABLE DOCUMENTS

2.1 <u>Government specification, standards, and handbooks</u>. The following specification, standards, and handbooks form a part of this drawing to the extent specified herein. Unless otherwise specified, the issues of these documents are those cited in the solicitation or contract.

#### DEPARTMENT OF DEFENSE SPECIFICATION

MIL-PRF-38535 - Integrated Circuits, Manufacturing, General Specification for.

#### DEPARTMENT OF DEFENSE STANDARDS

MIL-STD-883 - Test Method Standard Microcircuits.

MIL-STD-1835 - Interface Standard Electronic Component Case Outlines.

# DEPARTMENT OF DEFENSE HANDBOOKS

MIL-HDBK-103 - List of Standard Microcircuit Drawings.

MIL-HDBK-780 - Standard Microcircuit Drawings.

(Copies of these documents are available online at <u>http://assist.daps.dla.mil/quicksearch/</u> or <u>http://assist.daps.dla.mil</u> or from the Standardization Document Order Desk, 700 Robbins Avenue, Building 4D, Philadelphia, PA 19111-5094.)

2.2 <u>Non-Government publications</u>. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those cited in the solicitation or contract.

# ELECTRONIC INDUSTRIES ALLIANCE (EIA)

JEDEC Standard No. 20 - Standard for Description of 54/74ACXXXX and 54/74ACTXXXX Advanced High-Speed CMOS Devices

(Copies of these documents are available on line at <u>http://www/jedec.org</u> or from Electronic Industries Alliance, 2500 Wilson Boulevard, Arlington, VA 22201-3834).

2.3 <u>Order of precedence</u>. In the event of a conflict between the text of this drawing and the references cited herein, the text of this drawing takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

#### 3. REQUIREMENTS

3.1 <u>Item requirements</u>. The individual item requirements for device classes Q and V shall be in accordance with MIL-PRF-38535 and as specified herein or as modified in the device manufacturer's Quality Management (QM) plan. The modification in the QM plan shall not affect the form, fit, or function as described herein. The individual item requirements for device class M shall be in accordance with MIL-PRF-38535, appendix A for non-JAN class level B devices and as specified herein.

3.2 <u>Design, construction, and physical dimensions</u>. The design, construction, and physical dimensions shall be as specified in MIL-PRF-38535 and herein for device classes Q and V or MIL-PRF-38535, appendix A and herein for device class M.

STANDARD MICROCIRCUIT DRAWING	SIZE A		5962-89561
DEFENSE SUPPLY CENTER COLUMBUS		REVISION LEVEL	SHEET
COLUMBUS, OHIO 43218-3990		B	5

3.2.1 Case outlines. The case outlines shall be in accordance with 1.2.4 herein.

3.2.2 <u>Terminal connections</u>. The terminal connections shall be as specified on figure 1.

3.2.3 Truth table. The truth table shall be as specified on figure 2.

3.2.4 Logic diagram. The logic diagram shall be as specified on figure 3.

3.2.5 <u>Counting sequence</u>. The counting sequence shall be as specified on figure 4.

3.2.6 Switching waveforms and test circuit. The switching waveforms and test circuit shall be as specified on figure 5.

3.2.7 <u>Radiation exposure circuit</u>. The radiation exposure circuit shall be maintained by the manufacturer under document revision level control and shall be made available to the preparing or acquiring activity upon request.

3.3 <u>Electrical performance characteristics and postirradiation parameter limits</u>. Unless otherwise specified herein, the electrical performance characteristics and postirradiation parameter limits are as specified in table I and shall apply over the full case operating temperature range.

3.4 <u>Electrical test requirements</u>. The electrical test requirements shall be the subgroups specified in table II. The electrical tests for each subgroup are defined in table I.

3.5 <u>Marking</u>. The part shall be marked with the PIN listed in 1.2 herein. In addition, the manufacturer's PIN may also be marked. For packages where marking of the entire SMD PIN number is not feasible due to space limitations, the manufacturer has the option of not marking the "5962-" on the device. For RHA product using this option, the RHA designator shall still be marked. Marking for device classes Q and V shall be in accordance with MIL-PRF-38535. Marking for device class M shall be in accordance with MIL-PRF-38535, appendix A.

3.5.1 <u>Certification/compliance mark</u>. The certification mark for device classes Q and V shall be a "QML" or "Q" as required in MIL-PRF-38535. The compliance mark for device class M shall be a "C" as required in MIL-PRF-38535, appendix A.

3.6 <u>Certificate of compliance</u>. For device classes Q and V, a certificate of compliance shall be required from a QML-38535 listed manufacturer in order to supply to the requirements of this drawing (see 6.6.1 herein). For device class M, a certificate of compliance shall be required from a manufacturer in order to be listed as an approved source of supply in MIL-HDBK-103 (see 6.6.2 herein). The certificate of compliance submitted to DSCC-VA prior to listing as an approved source of supply for this drawing shall affirm that the manufacturer's product meets, for device classes Q and V, the requirements of MIL-PRF-38535 and herein or for device class M, the requirements of MIL-PRF-38535, appendix A and herein.

3.7 <u>Certificate of conformance</u>. A certificate of conformance as required for device classes Q and V in MIL-PRF-38535 or for device class M in MIL-PRF-38535, appendix A shall be provided with each lot of microcircuits delivered to this drawing.

3.8 <u>Notification of change for device class M</u>. For device class M, notification to DSCC-VA of change of product (see 6.2 herein) involving devices acquired to this drawing is required for any change that affects this drawing.

3.9 <u>Verification and review for device class M</u>. For device class M, DSCC, DSCC's agent, and the acquiring activity retain the option to review the manufacturer's facility and applicable required documentation. Offshore documentation shall be made available onshore at the option of the reviewer.

3.10 <u>Microcircuit group assignment for device class M</u>. Device class M devices covered by this drawing shall be in microcircuit group number 40 (see MIL-PRF-38535, appendix A).

STANDARD MICROCIRCUIT DRAWING	SIZE A		5962-89561
DEFENSE SUPPLY CENTER COLUMBUS COLUMBUS, OHIO 43218-3990		REVISION LEVEL B	SHEET 6

Test and MIL-STD-883 test method <u>1</u> /	Symbol Test conditions $2/$ -55°C $\leq$ T <sub>C</sub> $\leq$ +125° +3.0 V $\leq$ V <sub>CC</sub> $\leq$ +5.5		25°C	Device type and <u>4</u> /	V <sub>cc</sub>	Group A subgroups	Limits <u>5</u> /		Unit
Positive input		unless otherwise sp		device class			Min	Max	
Positive input clamp voltage 3022	V <sub>IC+</sub>	For input under test, $I_{IN} =$	1.0 mA	All V	0.0 V	1	0.4	1.5	V
Negative input clamp voltage 3022	V <sub>IC-</sub>	For input under test, I <sub>IN</sub> =	-1.0 mA	All V	Open	1	-0.4	-1.5	V
High level output voltage	V <sub>ОН</sub> <u>6</u> /	$V_{IN} = V_{IH}$ minimum or $V_{IL}$ $I_{OH} = -50 \ \mu A$	maximum	All All	3.0 V	1, 2, 3	2.9		V
3006				All All	4.5 V		4.4		
				All	5.5 V		5.4		
		$V_{IN} = V_{IH}$ minimum or $V_{IL}$ $I_{OH} = -4$ mA	maximum	All All All	3.0 V		2.4		_
		$V_{IN} = V_{IH}$ minimum or $V_{IL}$ $I_{OH} = -24$ mA	maximum	All All	4.5 V		3.7		-
				All All	5.5 V		4.7		
		$V_{IN} = V_{IH}$ minimum or $V_{IL}$ $I_{OH} = -50$ mA	maximum	All	5.5 V		3.85		
Low level output voltage 3007	V <sub>OL</sub> <u>6</u> /	$V_{IN} = V_{IH}$ minimum or $V_{IL}$ $I_{OL} = 50 \ \mu A$	maximum	All	3.0 V	1, 2, 3		0.1	V
	_			All All	4.5 V			0.1	
				All	5.5 V			0.1	
		$V_{IN} = V_{IH}$ minimum or $V_{IL}$ $I_{OL} = 12$ mA	maximum	All All	3.0 V			0.5	
		$V_{IN} = V_{IH}$ minimum or $V_{IL}$ $I_{OL} = 24$ mA	maximum	All All	4.5 V	-		0.5	
		$I_{OL} = 24 \text{ IIIA}$		All	5.5 V			0.5	-
		$V_{IN} = V_{IH}$ minimum or $V_{IL}$ $I_{OL} = 50$ mA	maximum	All All All	5.5 V			1.65	
High level input voltage	V <sub>IH</sub>			All	3.0 V	1, 2, 3	2.1		V
vollaye	<u>7</u> /			All All	4.5 V		3.15		1
				All	5.5 V		3.85		1
Low level input	V <sub>IL</sub>			All	3.0 V	1, 2, 3		0.9	V
voltage	<u>7</u> /			All	4.5 V	-		1.35	-
				All	5.5 V			1.65	-
See footnotes at end	of table.	1		All	<u> </u>			<u> </u>	<u> </u>
МІСР	STAND	ARD DRAWING	SIZ				5	5962-8	9561
DEFENSE S	UPPLY CEI	NTER COLUMBUS 0 43218-3990			REVISION	LEVEL B	SHE	EET	7

Test and MIL-STD-883 test method 1/	Symbol	Test conditions $2/3/$ -55°C $\leq$ T <sub>C</sub> $\leq$ +125°C +3.0 V $\leq$ V <sub>CC</sub> $\leq$ +5.5 V	Device type and <u>4</u> /	V <sub>cc</sub>	Group A subgroups	Lim	its <u>5</u> /	Un
·····		unless otherwise specified	device class			Min	Max	_
Input leakage current low 3009	IIL	V <sub>IN</sub> = 0.0 V	All All	5.5 V	1		-0.1	μΑ
					2, 3		-1.0	
Input leakage current high 3010	I <sub>IH</sub>	V <sub>IN</sub> = 5.5 V	All All	5.5 V	1		0.1	μA
<u></u>					2, 3		1.0	
Quiescent supply current, output	I <sub>CCH</sub>	$V_{IN} = V_{CC} \text{ or } GND$ $I_O = 0 \text{ A}$	All All	5.5 V	1 2, 3		4 80	μA
high 3005					2, 3		00	
		M, D, P, L, R, F <u>8</u> /			1		50	
Quiescent supply current, output	I <sub>CCL</sub>	$V_{IN} = V_{CC}$ or GND $I_O = 0$ A	All All	5.5 V	1		4	μA
low 3005					2,3		80	_
Input capacitance	C <sub>IN</sub>	M, D, P, L, R, F <u>8</u> / See 4.4.1c	01 All	5.0 V	1 4		50 8.0	pF
3012		$T_{\rm C}$ = +25°C	All				0.0	
Power dissipation capacitance	С <sub>РD</sub> <u>9</u> /	See 4.4.1c T <sub>C</sub> = +25°C, f = 1 MHz	All All	5.0 V	4		60.0	pF
Functional tests 3014	<u>10</u> /	See 4.4.1b $V_{IN} = V_{IH} \text{ or } V_{IL}$ Verify output $V_{OUT}$	All All	3.0 V	7, 8	L	Н	
				5.5 V	7, 8	L	Н	
Propagation delay time, high to low low to high, CP to Qn	t <sub>PHL1</sub> , t <sub>PLH1</sub> <u>11</u> /	$T_{C} = +25^{\circ}C$ $C_{L} = 50 \text{ pF minimum}$ $R_{L} = 500\Omega$ See figure 5	All All	3.0 V	9	1.0	12.0	ns
( <del>PE</del> = HIGH) 3003			All All	4.5 V		1.5	8.5	
		$T_{C}$ = -55°C and +125°C $C_{L}$ = 50 pF minimum $R_{L}$ = 500 $\Omega$	All All	3.0 V	10, 11	1.0	14.0	
		See figure 5	All	4.5 V	-	1.5	10.0	
Propagation delay	t	T <sub>c</sub> = +25°C	All	3.0 V	9	1.0	12.0	ns
time, high to low low to high,	t <sub>PHL2</sub> , t <sub>PLH2</sub> <u>11</u> /	$C_c = +25^{\circ}C$ $C_L = 50 \text{ pF minimum}$ $R_1 = 500\Omega$	All	3.0 V	9	1.0	12.0	
CP to Qn		See figure 5	All	4.5 V		1.5	8.5	1
(PE = LOW) 3003		$T_c = -55^{\circ}C$ and $+125^{\circ}C$	All	3.0 V	10, 11	1.0	14.0	-
		$C_L = 50 \text{ pF} \text{ minimum}$ $R_L = 500\Omega$	All					
		See figure 5	All All	4.5 V		1.5	10.0	
e footnotes at end c	f table.							
			SIZE A				5962-8	956 <sup>,</sup>
	PPLY CEN	DRAWING		REVISI	ON LEVEL	SI	HEET	-

Test and MIL-STD-883 test method <u>1</u> /	Symbol	Test conditions $2/3/$ -55°C $\leq$ T <sub>C</sub> $\leq$ +125°C +3.0 V $\leq$ V <sub>CC</sub> $\leq$ +5.5 V	Device type and <u>4</u> /	V <sub>CC</sub>	Group A subgroups	Lim	its <u>5</u> /	U
··· <u>-</u>		unless otherwise specified	device class			Min	Max	
Propagation delay time, high to low low to high, CP to TC	t <sub>PHL3</sub> <u>11</u> /	$T_{C} = +25^{\circ}C$ $C_{L} = 50 \text{ pF minimum}$ $R_{L} = 500\Omega$ See figure 5	All All	3.0 V	9	3.0	14.0	n
3003			All All	4.5 V		3.0	10.5	
	t <sub>PLH3</sub>		All All	3.0 V		3.0	14.0	
	<u>11</u> /		All	4.5 V		3.0	10.0	
	t <sub>PHL3</sub> <u>11</u> /	$T_{C} = -55^{\circ}C$ and $+125^{\circ}C$ $C_{L} = 50 \text{ pF minimum}$ $R_{L} = 500\Omega$ See figure 5	All All	3.0 V	10, 11	3.0	17.5	n
			All All	4.5 V		3.0	13.0	
	t <sub>PLH3</sub>		All All	3.0 V		3.0	18.0	
	<u>11</u> /		All All	4.5 V		3.0	13.0	
Propagation delay time, high to low low to high, CET to TC	t <sub>PHL4</sub> <u>11</u> /	$T_{C} = +25^{\circ}C$ $C_{L} = 50 \text{ pF minimum}$ $R_{L} = 500\Omega$ See figure 5	All All	3.0 V	9	1.0	11.5	n
3003			All All	4.5 V		1.5	8.5	
	t <sub>PLH4</sub>		All	3.0 V		1.0	10.0	
	<u>11</u> /		All	4.5 V		1.5	6.5	
	t <sub>PHL4</sub> <u>11</u> /	$T_{C} = -55^{\circ}C$ and $+125^{\circ}C$ $C_{L} = 50 \text{ pF}$ minimum $R_{L} = 500\Omega$ See figure 5	All All	3.0 V	10, 11	1.0	13.5	n
			All All	4.5 V		1.5	10.5	
	t <sub>PLH4</sub>		All All	3.0 V		1.0	13.0	
	<u>11</u> /		All All	4.5 V		1.5	8.5	
Propagation delay time, high to low MR to Qn	t <sub>PHL5</sub> <u>11</u> /	$T_{C} = +25^{\circ}C$ $C_{L} = 50 \text{ pF minimum}$ $R_{L} = 500\Omega$	All All	3.0 V	9	1.0	11.5	n
3003		See figure 5	All All	4.5 V		1.5	8.5	
		$T_{C} = -55^{\circ}C$ and $+125^{\circ}C$ $C_{L} = 50 \text{ pF}$ minimum	All All	3.0 V	10, 11	1.0	14.5	n
		$R_L = 500\Omega$ See figure 5	All All	4.5 V		1.5	10.5	
see footnotes at end	of table.							
MICDO			SIZE <b>A</b>				5962-8	956
DEFENSE SU	JPPLY CEN	DRAWING NTER COLUMBUS 0 43218-3990		REVISIO	DN LEVEL B	SI	HEET	9

		TABLE I. Electrical performance cha	aracteristics	<u>s</u> - Contin	ued.			
Test and MIL-STD-883 test method <u>1</u> /	Symbol	Test conditions $2/3/$ -55°C $\leq$ T <sub>C</sub> $\leq$ +125°C +3.0 V $\leq$ V <sub>CC</sub> $\leq$ +5.5 V	Device type and <u>4</u> /	V <sub>CC</sub>	Group A subgroups	Lim	its <u>5</u> /	Unit
		unless otherwise specified	device class			Min	Max	
Propagation delay	t <sub>PHL6</sub>	T <sub>C</sub> = +25°C	All	3.0 V	9	1.0	15.0	ns
time, high to low,		$C_L = 50 \text{ pF} \text{ minimum}$	All					
MR to TC	<u>11</u> /	$R_L = 500\Omega$	All	4.5 V		1.5	11.5	
3003		See figure 5	All					
		T <sub>C</sub> = -55°C and +125°C	All	3.0 V	10, 11	1.0	18.5	ns
		$C_{L} = 50 \text{ pF} \text{ minimum}$	All					
		$R_L = 500\Omega$	All	4.5 V		1.5	14.0	
		See figure 5	All					

- 1/ For tests not listed in the referenced MIL-STD-883 (e.g. V<sub>IH</sub>,V<sub>IL</sub>) utilize the general test procedure under the conditions listed herein. All inputs and outputs shall be tested, as applicable, to the tests in table I herein.
- 2/ Each input/output, as applicable shall be tested at the specified temperature for the specified limits. Output terminals not designated shall be high level logic, low level logic, or open, except as follows:
  - a.  $V_{IC}$  (pos) tests, the GND terminal can be open.  $T_C = +25^{\circ}C$ .
  - b.  $V_{IC}$  (neg) tests, the V<sub>CC</sub> terminal shall be open.  $T_C = +25^{\circ}C$ .
  - c. All I<sub>CC</sub> tests, the output terminal shall be open. When performing these tests, the current meter shall be placed in the circuit such that all current flows through the meter.
- 3/ RHA parts for device type 01 meet all levels M, D, P, L, R, and F of irradiation. Pre and post irradiation values are identical unless otherwise specified in table I. When performing post irradiation electrical measurements for any RHA level for any device,  $T_A = +25$  °C.
- 4/ The word "All" in the device type and device class column, means limits for all device types and classes.
- 5/ For negative and positive voltage and current values, the sign designates the potential difference in reference to GND and the direction of current flow, respectively; and the absolute value of the magnitude, not the sign, is relative to the minimum and maximum limits, as applicable, listed herein. All devices shall meet or exceed the limits specified in table I, as applicable, at 3.0 V  $\leq V_{CC} \leq 3.6$  V and 4.5 V  $\leq V_{CC} \leq 5.5$  V.
- $\underline{6}$ / The V<sub>OH</sub> and V<sub>OL</sub> tests shall be tested at V<sub>CC</sub> = 3.0 V and 4.5 V. The V<sub>OH</sub> and V<sub>OL</sub> tests are guaranteed, if not tested, for other values of V<sub>CC</sub>. Limits shown apply to operation at V<sub>CC</sub> = 3.3 V ±0.3 V and V<sub>CC</sub> = 5.0 V ±0.5 V. Tests with input current at +50 mA or -50 mA are performed on only one input at a time with duration not to exceed 10 ms. Transmission driving tests may be performed using V<sub>IN</sub> = V<sub>CC</sub> or GND. When V<sub>IN</sub> = V<sub>CC</sub> or GND is used, the test is guaranteed for V<sub>IN</sub> = V<sub>IH</sub> minimum and V<sub>IL</sub> maximum.
- <u>T</u>/ The V<sub>IH</sub> and V<sub>IL</sub> tests are not required if applied as forcing functions for V<sub>OH</sub> and V<sub>OL</sub> tests.
- <u>8</u>/ The maximum limit for this parameter at 100 krads (Si) is 4  $\mu$ A.
- 9/ Power dissipation capacitance (C<sub>PD</sub>) determines both the power consumption (P<sub>D</sub>) and dynamic current consumption (I<sub>s</sub>). Where:

f is the frequency of the input signal and CL is the external output load capacitance.

- <u>10</u>/ Tests shall be performed in sequence, attributes data only. Functional tests shall include the truth table and other logic patterns used for fault detection. The test vectors used to verify the truth table shall, at a minimum, test all functions of each input and output. All possible input to output logic patterns per function shall be guaranteed, if not tested, to the truth table in figure 2 herein. Functional tests shall be performed in sequence as approved by the qualifying activity on qualified devices. Allowable tolerances in accordance with MIL-STD-883 for the input voltage levels may be incorporated. For V<sub>OUT</sub> measurements, L  $\leq 0.3V_{CC}$  and H  $\geq 0.7V_{CC}$ .
- <u>11</u>/ AC limits at  $V_{CC} = 5.5$  V are equal to the limits at  $V_{CC} = 4.5$  V and guaranteed by testing at  $V_{CC} = 4.5$  V. AC limits at  $V_{CC} = 3.6$  V are equal to limits at  $V_{CC} = 3.0$  V and guaranteed by testing at  $V_{CC} = 3.0$  V. Minimum ac limits for  $V_{CC} = 5.5$  V are 1.0 ns and guaranteed by guardbanding the  $V_{CC} = 4.5$  V minimum limits to 1.5 ns. For propagation delay tests, all paths must be tested.

STANDARD MICROCIRCUIT DRAWING	SIZE A		5962-89561
DEFENSE SUPPLY CENTER COLUMBUS		REVISION LEVEL	SHEET
COLUMBUS, OHIO 43218-3990		B	10

Device type		
Case outlines	E, F, and X	2
Terminal	Terminal	symbol
number		
1	MR	NC
2	СР	MR
3	P0	CP
4	P1	P0
5	P2	P1
6	P3	NC
7	CEP	P2
8	GND	P3
9	PE	CEP
10	CET	GND
11	Q3	NC
12	Q2	PE
13	Q1	CET
14	Q0	Q3
15	TC	Q2
16	V <sub>cc</sub>	NC
17		Q1
18		Q0
19		тс
20		V <sub>CC</sub>

FIGURE 1. Terminal connections.

STANDARD MICROCIRCUIT DRAWING	SIZE <b>A</b>		5962-89561
DEFENSE SUPPLY CENTER COLUMBUS		REVISION LEVEL	SHEET
COLUMBUS, OHIO 43218-3990		A	11

	Inp	outs		Action on rising
MR	PE	CET	CEP	clock edge
L	Х	Х	Х	Reset (clear)
н	L	Х	Х	Load (Pn to Qn)
н	н	н	Н	Count (increment)
Н	Н	L	Х	No change (hold)
н	Н	Х	L	No change (hold)


H = High voltage level

L = Low voltage level

X = Irrelevant

FIGURE 2. Truth table.

STANDARD MICROCIRCUIT DRAWING	SIZE <b>A</b>		5962-89561
DEFENSE SUPPLY CENTER COLUMBUS		REVISION LEVEL	SHEET
COLUMBUS, OHIO 43218-3990		A	12





Downloaded from Arrow.com.


Sequence illustrated in waveforms:


- 1. Reset outputs to zero.
- 2. Preset to binary twelve.
- 3. Count to thirteen, fourteen, fifteen, zero, one, and two.

4. Inhibit.









NOTES :

- 1.
- 2.
- .  $C_L = 50 \text{ pF}$  or equivalent, (includes probe and jig capacitance).  $R_T = 50\Omega$  or equivalent.  $R_L = 500\Omega$  or equivalent. Input signal from pulse generator:  $V_{IN} = 0.0 \text{ V}$  to  $V_{CC}$ ; PRR  $\leq 1 \text{ MHz}$ ;  $Z_O = 50\Omega$ ;  $t_r \leq 3.0 \text{ ns}$ ;  $t_f \leq 3.0 \text{ ns}$ ;  $t_r$  and  $t_r$  shall be measured from 10% of  $V_{CC}$  to 90% of  $V_{CC}$  and from 90% of  $V_{CC}$  to 10% of  $V_{CC}$ , respectively; 3. duty cycle = 50 percent.
- Timing parameters shall be tested at a minimum input frequency of 1 MHz. 4.
- 5. The outputs are measured one at a time with one transition per measurement.

FIGURE 5. Switching waveforms and test circuit - Continued.

STANDARD MICROCIRCUIT DRAWING	SIZE A		5962-89561
DEFENSE SUPPLY CENTER COLUMBUS COLUMBUS, OHIO 43218-3990		REVISION LEVEL B	SHEET 17
DSCC FORM 2234		5	17

APR 97

## 4. VERIFICATION

4.1 <u>Sampling and inspection</u>. For device classes Q and V, sampling and inspection procedures shall be in accordance with MIL-PRF-38535 or as modified in the device manufacturer's Quality Management (QM) plan. The modification in the QM plan shall not affect the form, fit, or function as described herein. For device class M, sampling and inspection procedures shall be in accordance with MIL-PRF-38535, appendix A.

4.2 <u>Screening</u>. For device classes Q and V, screening shall be in accordance with MIL-PRF-38535, and shall be conducted on all devices prior to qualification and technology conformance inspection. For device class M, screening shall be in accordance with method 5004 of MIL-STD-883, and shall be conducted on all devices prior to quality conformance inspection.

#### 4.2.1 Additional criteria for device class M.

- a. Burn-in test, method 1015 of MIL-STD-883.
  - (1) Test condition A, B, C, or D. The test circuit shall be maintained by the manufacturer under document revision level control and shall be made available to the preparing or acquiring activity upon request. The test circuit shall specify the inputs, outputs, biases, and power dissipation, as applicable, in accordance with the intent specified in method 1015 of MIL-STD-883.
  - (2)  $T_A = +125^{\circ}C$ , minimum.
- b. Interim and final electrical test parameters shall be as specified in table II herein.

## 4.2.2 Additional criteria for device classes Q and V.

- a. The burn-in test duration, test condition and test temperature, or approved alternatives shall be as specified in the device manufacturer's QM plan in accordance with MIL-PRF-38535. The burn-in test circuit shall be maintained under document revision level control of the device manufacturer's Technology Review Board (TRB) in accordance with MIL-PRF-38535 and shall be made available to the acquiring or preparing activity upon request. The test circuit shall specify the inputs, outputs, biases, and power dissipation, as applicable, in accordance with the intent specified in method 1015 of MIL-STD-883.
- b. Interim and final electrical test parameters shall be as specified in table II herein.
- c. Additional screening for device class V beyond the requirements of device class Q shall be as specified in MIL-PRF-38535, appendix B.

4.3 <u>Qualification inspection for device classes Q and V</u>. Qualification inspection for device classes Q and V shall be in accordance with MIL-PRF-38535. Inspections to be performed shall be those specified in MIL-PRF-38535 and herein for groups A, B, C, D, and E inspections (see 4.4.1 through 4.4.4).

4.4 <u>Conformance inspection</u>. Technology conformance inspection for classes Q and V shall be in accordance with MIL-PRF-38535 including groups A, B, C, D, and E inspections and as specified herein. Quality conformance inspection for device class M shall be in accordance with MIL-PRF-38535, appendix A and as specified herein. Inspections to be performed for device class M shall be those specified in method 5005 of MIL-STD-883 and herein for groups A, B, C, D, and E inspections (see 4.4.1 through 4.4.4).

STANDARD MICROCIRCUIT DRAWING	SIZE A		5962-89561
DEFENSE SUPPLY CENTER COLUMBUS COLUMBUS, OHIO 43218-3990		REVISION LEVEL B	SHEET 18

Test requirements	Subgroups (in accordance with MIL-STD-883, method 5005, table I)	Subgroups (in accordance with MIL-PRF-38535, table III)	
	Device class M	Device class Q	Device class V
Interim electrical parameters (see 4.2)			1
Final electrical parameters (see 4.2)	<u>1</u> / 1, 2, 3, 7, 8, 9	<u>1</u> / 1, 2, 3, 7, 8, 9	<u>2/, 3/</u> 1, 2, 3, 7, 8, 9, 10, 11
Group A test requirements (see 4.4)	1, 2, 3, 4, 7, 8, 9, 10, 11	1, 2, 3, 4, 7, 8, 9, 10, 11	1, 2, 3, 4, 7, 8, 9, 10, 11
Group C end-point electrical parameters (see 4.4)	1, 2, 3	1, 2, 3	<u>3</u> / 1, 2, 3, 7,8, 9, 10, 11
Group D end-point electrical parameters (see 4.4)	1, 2, 3	1, 2, 3	1, 2, 3
Group E end-point electrical parameters (see 4.4)	1, 7, 9	1, 7, 9	1, 7, 9

# TABLE II. Electrical test requirements.

 <u>1</u>/ PDA applies to subgroup 1.
 <u>2</u>/ PDA applies to subgroups 1, 7, and deltas.
 <u>3</u>/ Delta limits, as specified in table III, shall be required where specified, and the delta limits shall be completed with reference to the zero hour electrical parameters.

Parameter <u>1</u> /	Symbol	Delta Limits
Quiescent supply current	I <sub>CCH</sub> , I <sub>CCL</sub>	±300 nA
Input current low level	I <sub>IL</sub>	±20 nA
Input current high level	I <sub>IH</sub>	±20 nA
Output voltage low level $V_{CC} = 5.5 \text{ V}$ $I_{OL} = 24 \text{ mA}$	V <sub>OL</sub>	±0.04 V
Output voltage high level $V_{CC} = 5.5 V$ $I_{OH} = -24 mA$	V <sub>он</sub>	±0.2 V

TABLE III. Burn-in and operating life test, delta parameters (+25°C).

1/ These parameters shall be recorded before and after the required burn-in and life tests to determine the delta limits.

STANDARD MICROCIRCUIT DRAWING	SIZE A		5962-89561
DEFENSE SUPPLY CENTER COLUMBUS		REVISION LEVEL	SHEET
COLUMBUS, OHIO 43218-3990		B	19

#### 4.4.1 Group A inspection.

a. Tests shall be as specified in table II herein.

- b. For device class M, subgroups 7 and 8 tests shall be sufficient to verify the truth table in figure 2 herein. The test vectors used to verify the truth table shall, at a minimum, test all functions of each input and output. All possible input to output logic patterns per function shall be guaranteed, if not tested, to the truth table in figure 2, herein. For device classes Q and V, subgroups 7 and 8 shall include verifying the functionality of the device.
- c. C<sub>IN</sub> and C<sub>PD</sub> shall be measured only for initial qualification and after process or design changes which may affect capacitance. C<sub>IN</sub> shall be measured between the designated terminal and GND at a frequency of 1 MHz. C<sub>PD</sub> shall be tested in accordance with the latest revision of JEDEC Standard No. 20 and table I herein. For C<sub>IN</sub> and C<sub>PD</sub>, test all applicable pins on five devices with zero failures.

4.4.2 Group C inspection. The group C inspection end-point electrical parameters shall be as specified in table II herein.

- 4.4.2.1 Additional criteria for device class M. Steady-state life test conditions, method 1005 of MIL-STD-883:
  - a. Test condition A, B, C, or D. The test circuit shall be maintained by the manufacturer under document revision level control and shall be made available to the preparing or acquiring activity upon request. The test circuit shall specify the inputs, outputs, biases, and power dissipation, as applicable, in accordance with the intent specified in method 1005 of MIL-STD-883.
  - b.  $T_A = +125^{\circ}C$ , minimum.
  - c. Test duration: 1,000 hours, except as permitted by method 1005 of MIL-STD-883.

4.4.2.2 Additional criteria for device classes Q and V. The steady-state life test duration, test condition and test temperature, or approved alternatives shall be as specified in the device manufacturer's QM plan in accordance with MIL-PRF-38535. The test circuit shall be maintained under document revision level control by the device manufacturer's TRB in accordance with MIL-PRF-38535 and shall be made available to the acquiring or preparing activity upon request. The test circuit shall specify the inputs, outputs, biases, and power dissipation, as applicable, in accordance with the intent specified in method 1005 of MIL-STD-883.

4.4.3 Group D inspection. The group D inspection end-point electrical parameters shall be as specified in table II herein.

4.4.4 <u>Group E inspection</u>. Group E inspection is required only for parts intended to be marked as radiation hardness assured (see 3.5 herein).

- a. End-point electrical parameters shall be as specified in table II herein.
- b. For device classes Q and V, the devices or test vehicle shall be subjected to radiation hardness assured tests as specified in MIL-PRF-38535 for the RHA level being tested. For device class M, the devices shall be subjected to radiation hardness assured tests as specified in MIL-PRF-38535, appendix A for the RHA level being tested. All device classes must meet the postirradiation end-point electrical parameter limits as defined in table I at  $T_A = +25^{\circ}C \pm 5^{\circ}C$ , after exposure, to the subgroups specified in table II herein.
- c. RHA tests for device classes M, Q, and V for levels M, D, P, L, R, and F shall be performed through each level to determine at what levels the devices meet the RHA requirements. These RHA tests shall be performed for initial qualification and after design or process changes which may affect the RHA performance of the device.
- d. Prior to irradiation, each selected sample shall be assembled in its qualified package. It shall pass the specified group A electrical parameters in table I for subgroups specified in table II herein.

STANDARD MICROCIRCUIT DRAWING DEFENSE SUPPLY CENTER COLUMBUS COLUMBUS, OHIO 43218-3990	SIZE A		5962-89561
		REVISION LEVEL B	SHEET 20

4.4.4.1 <u>Total dose irradiation testing</u>. Total dose irradiation testing shall be performed in accordance with MIL-STD-883, method 1019, condition A and as specified herein. Prior to and during total dose irradiation characterization and testing, the devices for characterization shall be biased so that 50 percent are at inputs high and 50 percent are at inputs low, and the devices for testing shall be biased to the worst case condition established during characterization. Devices shall be biased as follows:

a. Inputs tested high,  $V_{CC}$  = 5.5 V dc ±5%,  $V_{IN}$  = 5.0 V dc +10%,  $R_{IN}$  = 1 k $\Omega$  ±20%, and all outputs are open.

b. Inputs tested low, V<sub>CC</sub> = 5.5 V dc  $\pm$ 5%, V<sub>IN</sub> = 0.0 V dc, R<sub>IN</sub> = 1 k $\Omega \pm$ 20%, and all outputs are open.

4.4.4.1.1 <u>Accelerated aging test</u>. Accelerated aging shall be performed on classes M, Q, and V devices requiring an RHA level greater than 5K rads (Si). The post-anneal end-point electrical parameter limits shall be as specified in table I herein and shall be the preirradiation end-point electrical parameter limit at  $25^{\circ}C \pm 5^{\circ}C$ . Testing shall be performed at initial qualification and after any design or process changes which may affect the RHA response of the device.

4.5 <u>Methods of inspection</u>. Methods of inspection shall be specified as follows:

4.5.1 <u>Voltage and current</u>. Unless otherwise specified, all voltages given are referenced to the microcircuit GND terminal. Currents given are conventional current and positive when flowing into the referenced terminal.

5. PACKAGING

5.1 <u>Packaging requirements</u>. The requirements for packaging shall be in accordance with MIL-PRF-38535 for device classes Q and V or MIL-PRF-38535, appendix A for device class M.

#### 6. NOTES

6.1 <u>Intended use</u>. Microcircuits conforming to this drawing are intended for use for Government microcircuit applications (original equipment), design applications, and logistics purposes.

6.1.1 <u>Replaceability</u>. Microcircuits covered by this drawing will replace the same generic device covered by a contractorprepared specification or drawing.

6.1.2 Substitutability. Device class Q devices will replace device class M devices.

6.2 <u>Configuration control of SMD's</u>. All proposed changes to existing SMD's will be coordinated with the users of record for the individual documents. This coordination will be accomplished using DD Form 1692, Engineering Change Proposal.

6.3 <u>Record of users</u>. Military and industrial users should inform Defense Supply Center Columbus (DSCC) when a system application requires configuration control and which SMD's are applicable to that system. DSCC will maintain a record of users and this list will be used for coordination and distribution of changes to the drawings. Users of drawings covering microelectronic devices (FSC 5962) should contact DSCC-VA, telephone (614) 692-0544.

6.4 <u>Comments</u>. Comments on this drawing should be directed to DSCC-VA, Columbus, Ohio 43218-3990, or telephone (614) 692-0547.

6.5 <u>Abbreviations, symbols, and definitions</u>. The abbreviations, symbols, and definitions used herein are defined in MIL-PRF-38535 and MIL-HDBK-1331.

6.6 Sources of supply.

6.6.1 <u>Sources of supply for device classes Q and V</u>. Sources of supply for device classes Q and V are listed in QML-38535. The vendors listed in QML-38535 have submitted a certificate of compliance (see 3.6 herein) to DSCC-VA and have agreed to this drawing.

6.6.2 <u>Approved sources of supply for device class M</u>. Approved sources of supply for class M are listed in MIL-HDBK-103. The vendors listed in MIL-HDBK-103 have agreed to this drawing and a certificate of compliance (see 3.6 herein) has been submitted to and accepted by DSCC-VA.

STANDARD MICROCIRCUIT DRAWING	SIZE A		5962-89561
DEFENSE SUPPLY CENTER COLUMBUS		REVISION LEVEL	SHEET
COLUMBUS, OHIO 43218-3990		B	21

Downloaded from Arrow.com.

#### STANDARD MICROCIRCUIT DRAWING BULLETIN

## DATE: 04-12-14

Approved sources of supply for SMD 5962-89561 are listed below for immediate acquisition information only and shall be added to MIL-HDBK-103 and QML-38535 during the next revision. MIL-HDBK-103 and QML-38535 will be revised to include the addition or deletion of sources. The vendors listed below have agreed to this drawing and a certificate of compliance has been submitted to and accepted by DSCC-VA. This information bulletin is superseded by the next dated revision of MIL-HDBK-103 and QML-38535. DSCC maintains an online database of all current sources of supply at <a href="http://www.dscc.dla.mil/Programs/Smcr/">http://www.dscc.dla.mil/Programs/Smcr/</a>.

	-	
Standard microcircuit drawing PIN <u>1</u> /	Vendor CAGE number	Vendor similar PIN <u>2</u> /
5962-8956101EA	27014	54AC161DMQB
5962-8956101FA	27014	54AC161FMQB
5962-89561012A	27014	54AC161LMQB
5962-8956101XA	F8859	54AC161K02Q
5962-8956101VXA	F8859	54AC161K02V
5962-8956101XC	F8859	54AC161K01Q
5962-8956101VXC	F8859	54AC161K01V
5962F8956101XA	F8859	RHFAC161K02Q
5962F8956101VXA	F8859	RHFAC161K02V
5962F8956101XC	F8859	RHFAC161K01Q
5962F8956101VXC	F8859	RHFAC161K01V

- 1/ The lead finish shown for each PIN representing a hermetic package is the most readily available from the manufacturer listed for that part. If the desired lead finish is not listed contact the vendor to determine its availability.
- 2/ <u>Caution</u>. Do not use this number for item acquisition. Items acquired to this number may not satisfy the performance requirements of this drawing.

Vendor CAGE number	Vendor name and address
27014	National Semiconductor 2900 Semiconductor Drive P. O. Box 58090 Santa Clara, CA 95052-8090
F8859	ST Microelectronics 3 rue de Suisse BP4199

35041 RENNES cedex2-FRANCE

The information contained herein is disseminated for convenience only and the Government assumes no liability whatsoever for any inaccuracies in the information bulletin.